



[keller.com](https://www.keller.com)

Ralph B. Peck Lecture

November 6, 2025

John R. Wolosick, PE, SE, BC.GE, F.ASCE
Keller North America
Atlanta, GA




GEO-
INSTITUTE

Dr. Ralph Brazelton Peck

- Professor University of Illinois at Urbana-Champaign
- Retired from U of I 1974
- Eminent Consultant/Geotechnical Engineer
- Mentee of Karl Terzaghi
- Co Author: Terzaghi & Peck, Terzaghi, Peck and Mesri Soil Mechanics in Engineering Practice
- Developed Graduate Course CEE 584 Geotechnical Case Histories Required 1 Page Summaries



Ralph Peck,
Walter Hanson,
Reza Mesri



Reza Mesri,
Ralph Peck,
H.O. Ireland



keller.com



Slope Stabilization using Tall Soil Nail Walls at Natchez National Cemetery and Teton Pass

John R. Wolosick, PE, SE, BC.GE,
F.ASCE

Case Histories: Two Major Landslides Repaired using Soil Nailing

1. Natchez National Cemetery, 2021-2023

Client: US Army Corps of Engineers

Wall Length = 1,270 LF

Wall Height = 48 ft max, 31.5 ft avg

Wall Area = 40,000 Square Feet

\$9.8M General Contract



2. Teton Pass Landslide – ‘Big Fill Slide,’ 2024-2025

Owner: Wyoming Department of Transportation

Wall Length = 525 LF


Wall Height = 110 ft in corner

Wall Area = 60,000 Square Feet

**\$6.6M soil nailing, \$2.2M micropiles
Subcontract**



Natchez National Cemetery



- The city of Natchez lies on the southwestern border of Mississippi and is the oldest city on the Mississippi River.
- The Natchez National Cemetery is located on the Bluff overlooking the Mississippi River on the North side of the city and was established after two Civil War engagements in 1863 and 1864 at this location. The Cemetery was listed in the National Register of Historic Places in 1999. It is open for burials of all members of the armed forces.

Previous Slide Repairs in Natchez, Mississippi for the City of Natchez and the US Army Corps of Engineers

Clifton Avenue and Learneds Mill Road

74 foot tall Soil Nail Walls
with Tieback Anchors and
MSE wall. 1997-1999.




Natchez Under the Hill Rosalie Mansion and Silver Street

Soil Nail Wall with Tieback Anchors
2000-2001.



Major Erosion Event 2021



Major Erosion Event 2021



Geotechnical Conditions




Anchored Soil Nail Wall Solution

River side


Main Erosion Area

- 40,000 SF
- 1,270 LF
- Max H = 48 FT




Cemetery

Some Design Sections




Design Section Bs - Effective Stress Internal




Design Section Bs - Effective Stress Seismic

Some Design Sections





Design Section Bs - Total Stress Internal Stability



Design Section Bs - Total Stress Seismic

Anchored Soil Nail Wall Solution

- 7 rows of 40 ft to 50 ft soil nails
- 6' x 6' and 7.5' x 6' Spacings
- 1 row of Ground Anchors of 150 to 180 LF at base for Global Stability
- Shotcreted Anchor Reaction Beam
- Top two lifts vertical
- Remaining lifts battered at 20 degrees



Separation of Work Area from Public Area



Demolition of MSE Wall and Pavilion adjacent to Erosion Area



First Lift Construction – Vertical Lifts



Sacrificial Test Nails to Confirm Assumed Bond Stress



Remaining Wall Construction – Battered Lifts



Bottom of Wall Reinforcement and Drainage Details including Deep Tieback Anchor Locations



Shotcrete Tieback Anchor Reaction Beam



Steel Strand Tieback Anchors – 4-7 Strands - 245 kip max Spacing varies 6ft, 9ft, 10ft c-c




Tricky Outside Corner



Rebuilt MSE Wall (subcontract) above Soil Nail Wall and Wall Staining




New Storm Drainage






Teton Pass Highway 22





- Teton Pass Wyoming Highway 22 is a major road connecting Wyoming and Idaho. Thousands of people commute between Eastern Idaho and Northwestern Wyoming every day.
- A mudslide took place June 7th, 2024 on part of Highway 22 leading WYDOT to close the road. The following day, a slope failed about 2.5 miles East causing a landslide and washing out part of the road. There were no casualties since the road was already closed, but the driving time for commuters tripled.
- Keller was hired by Ames to provide soil nail temporary slope stabilization and permanent micropile shear pins.

Previous Slide Repairs at Snake River Canyon Wyoming DOT



Blue Trail Slide
Micropile Walls with Tieback
Anchors and MSE wall.
1997.



The Elbow Slide
Soil Nail walls with MSE
Wall. 1998-1999.

Previous Slide Repairs for WYDOT – Blue Trail Slide



- Upper, intermediate and lower walls constructed
- Micropiles used to construct the “A” portion of the walls
- Strand anchors also used for tieback elements

Previous Slide Repairs for WYDOT – Elbow Slide



- Upper and lower soil nail walls
- Shotcrete facing for lower wall
- Temporary steel mesh for upper wall
- Upper wall was relied on through winter
- MSE wall constructed in front of upper soil nail wall the following season

CMGC Proposal

- Keller teamed up with Ames Construction
- CMGC = Construction Manager General Contractor
- Collaborative process whereby the Contractor works with the Owner to develop solution, design and estimate cost concurrently
- Final cost proposal reviewed and verified by ICE (Independent Cost Estimator)



Wyoming Department of Transportation

Construction Manager/General Contractor (CM/GC)

SERVICES FOR

WYO 22 Big Fill Slide ND 32401



JULY 9, 2024

Submitted by Ames Construction, Inc.
In association with Keller North America




Ames Construction



Not a bad place to work!



Teton Range



North to
Yellowstone NP



Jackson Lake



Jenny Lake



Jackson Hole
Ski Resort



Jobsite

Mudslide on Teton Pass Hwy 22



Teton Pass Highway 22 Landslide



BEFORE



AFTER

Teton Pass Highway 22 Landslide



Teton Pass Highway 22 Landslide




AP

JACKSON, WYOMING



10
WIND 8


Teton Pass Highway 22 detour




- WYDOT opened a temporary detour in 3 weeks after the failure while working toward a full repair on the same section of the highway.
- The pass typically has grades of 10%, but the detour section increases to 11.3%.
- The failed section of the road will be rebuilt at its previous location once the permanent slope stabilization is completed.

FINAL PLAN – replace embankment with lightweight fill, geogrid, improved drainage and micropile shear support at base

- 1.25H:1V Excavation adjacent to detoured roadway
- Depth of Excavation = 100 ft +
- Time of Construction greatly reduced due to winter weather threat
- Temporary Shoring by Contractor
- Soil Nailing was performed 24/7
- Final Design by RJ Engineering for WYDOT




Temporary Shoring Plan



- Temporary shoring solution consists of about 60,000 SF of geotextile and wire mesh facing and 583 (as-built) soil nails, 40-50 ft long.
- L- shaped wall lengths were 410 ft and 115 ft, respectively
- The temporary slope parallel to the road was 1.25(H):1(V) ratio, and 1(H):1(V) ratio perpendicular to the highway


Temporary Shoring – Soil Nailing




- Notes from boring 24-12 (not sampled) modified design section
- Maximum soil nail length is 50 ft
- Installed on 10 ft horizontal and 7 ft vertical spacing
- Staggered diamond pattern
- Inclined 20 degrees from horizontal
- Geotextile and steel mesh facing with horizontal steel bar wales

Some Design Sections

Right Side of Cut: 1.25(H):1.0(V)
Pre-Failure Back Analysis
FS = 1.15 (note: initially lower)




After Soil Nailing
FS = 1.31




Some Design Sections

Left Side of Cut: 1.0(H):1.0(V)
Pre-Failure Back Analysis
FS = 0.88




After Soil Nailing
FS = 1.3




Soil Nail Drilling

- 25 ft and 14 ft masts with top drive drill heads mounted on 20 ton excavators.
- Ishebeck Titan Hollow Bar soil nails 40/20



Soil Nail Detail





Soil Nail Facing

- High strength wire mesh facing with parallel steel reinforcing bars acting as wales
- Geotextile fabric on the backside against the soil



Soil Nail Facing Detail



Facing Installation Process



Step 1: Place and secure geotextile.



Step 2: Place wire mesh sheet.



Step 3: Tie wire mesh properly.



Step 4: Place and tie continuous waler bar.



Step 5: Place bearing plate, beveled washer, and collar nut.

Excavation

- GC Ames Construction had excavation crews working day and night.
- Utilized a conveyor belt, 3 excavators, and 1 dozer to move soil.



1 Test Nail per Lift




Teton Pass Temporary Shoring Completed in 5 weeks working 24/7




Horizontal Drains

- **5 Horizontal Drains Installed after Soil Nailing by Jensen Drilling**



Horizontal Drains

- 2 inch diameter slotted pipe
- Drilled 90 ft
- 10 ft riser section
- 5 degrees upward




Horizontal Drain Drilling




Permanent Slope Stability Micropiles

- Keller installed 140 permanent micropiles for base stabilization in front of the shoring
- 9-5/8 inch diameter cement grouted steel pipes and bars
- 2 groups of coupled micropiles with 2 rows in each group
- RJ Engineering design for WYDOT




Permanent Slope Stability Micropiles

- Approx. 8 ft of pipe was left sticking up from the ground
- Micropiles connected to the future reinforced backfill slope by Ames
- Ames to install a leveling pad with rock (up to 6 in.) to the bottom of pier cap.
- Reinforced lightweight foamed glass aggregate backfill with biaxial geogrid up to the previous highway elevation



Permanent Slope Stability Micropiles

- Micropiles in each group are connected by a 5ft x 4ft pile cap
- MP Total length: 50 ft minimum
- Steel Pipe (9-5/8in): 35 ft
- 10 ft C-C spacing on pairs
- Rock Socket (8in): 15 ft minimum
- #14 – 75 ksi threadbar in the center
- Test Pits confirmed conditions after soft clay encountered in drilling




Micropile Installation



Micropile Testing



- 3 tension tests performed on sacrificial piles constructed using the same means and methods as for the production piles.
- 110 Kip Test Load; 55 Kip Design Load



Permanent Slope Stability Micropiles



Permanent Slope Stability Micropiles Completed in 3 weeks with 2 crews/2 rigs Working 1 long shift 6 days/week



Conditions at Site as Keller Demobilized



Conditions at Site as GC Ames Construction placed Lightweight Fill



December Conditions at Site – Weather Halted Project



2025 Completion of Project



Finishing the project – US Forest Service required covering of wall with soil to be grassed

Jackson Hole News & Guide



Acknowledgements:

Keller:

Jeff Bacon, Project Manager
Jesus Treto, PE, Project Executive
Joe Cavey, PE, Vice President
Joe Harris, Vice President
Ryan Smith, PE, Vice President – Special Projects
Jose Araiza, Site Engineer
Michael Capraro, Business Development Manager

Burns Cooley Dennis:

Brad Campbell, PE
Alex Reeb, Ph.D, PE

Ames Construction:

Kole Murray, PE, Vice President of Engineering
Rob Wise, Project Manager

WYDOT:

Bob Hammond, Resident Engineer
James Dahill, PG, Chief Engineering Geologist

Superintendents:

Miguel Castillo
Luis Ibarra
Donnie Cupstid
Chris Richardson

End

