



University of Kansas
David Booth Memorial Stadium


The Gateway District - Phase 1

HNTB Architecture
Structure's Group

March 5, 2026




71th Annual Structural Engineer Conference



Today's Topics

- History of Memorial Stadium
- Project Overview
- Project Schedule
- Project Challenges
- Lessons Learned
- Q&A



History of Memorial Stadium

- Built in 1921 - \$460k
- WWI Memorial
- Upper bowl added in the 60's
- Press Box & Suites in the 90's
- AFFC built in 2009
- Indoor Practice Facility - 2019



History of Memorial Stadium

- 1923 ACI 19th Annual Convention
- 632 by 464 ft and 47ft high
- Resembles Harvard Stadium & the Coliseum at Rome
- 30,000 seat capacity
- Reinforce concrete used
- Steel too costly
- Unit Construction Co. of St. Louis




Project Overview

Phase 1

- AFFC Renovation and Expansion
- New West Sideline
- New North Endzone & Conference Center
- New Scoreboard

District – Phase 1



Project Overview

Phase 2

- East Sideline
- South endzone

District – Phase 2

Project Overview

Anderson Family Football Complex (AFFC)



Project Overview

AFFC

- Tie AFFC into the stadium
- New Meeting Rooms
- New Coach's Office
- Added Lower Bowl Seating
- New Multi-purpose Rooms
- Refresh interior spaces


ROYAL
GALAM

ANDERSON FAMILY FOOTBALL COMPLEX


← ELEVATORS
← EMOTIONAL LOUNGE
← TRADITIONAL SEATING
← MEMBER SUITE



← TEAM MEETING ROOM
← RECRUITING LOUNGE →



Phase 1 - Complete




HNTB











A close-up photograph of several golden wheat stalks, showing the intricate details of the grain heads. The lighting is warm, highlighting the texture of the wheat. The background is softly blurred, creating a sense of depth.


Project Overview

Stadium

Project Overview

Phase 1

- Brings Fans Closer To The Field
- New Clubs
- New Suites & Press
- VIP Entrance
- Enhance Arrival Experience
- Year-round events
- New Conference Center





Existing

HNTB



New – Closer to the Action / More Diverse





In-Game Experience

HNTB



North Endzone - Existing



North Conference Center + Field Club



COMPLETED

~~In Progress~~ - VIP Lobby

HNTB



COMPLETED
~~In Progress~~ - Limestone Club

HNTB



COMPLETED
~~In Progress~~ – Suite Level Arrival



COMPLETED
~~In Progress~~ – Traditional Suites



COMPLETED
~~In Progress~~ – Founders Lounge

Project Overview

Structure

- ✓ 2018 IBC / ASCE 7-16
- ✓ Drilled Shaft Foundations
- ✓ Structural Steel Frame
- ✓ Precast Bowl Seating
- ✓ A913 Grade 65 for Cols > 100plf
- ✓ Lateral System
 - ✓ SCBF
 - ✓ Sway Frames
 - ✓ Precast Shear Walls



Project Overview

Key Stats

- \$340M Construction Cost
- 40,000 seats
- 4300 Total Tons of Steel
- 12 months from IFC to Final Steel
- 23 months from IFC to Opening



Project Schedule

Then a CMAR was hired....

- Turner hired in the end April '23
- Completely changed the design schedule
- We need to bid steel now!!



Project Schedule

- Summary of Quantities
- Primary Steel Only
- Based on a Schematic Design and issued following VE studies
- Excluded Many items
- Estimated 3992 tons
- Went from 5 FTEs to 10 FTEs

SUMMARY

BUILDING	STRUCTURAL COMPONENT	TONNAGE (TONS)	REMARKS
STADIUM	MAIN CONCOURSE	317	REF: SHEET S851
STADIUM	LOWER BOWL SEATING	256	REF: SHEET S851
STADIUM	WEST EXTERIOR PLAZA	81	REF: SHEET S851
STADIUM	NORTH ROOF	45	REF: SHEET S851
STADIUM	MECH YARD	23	REF: SHEET S851
STADIUM	MAIN CONCOURSE ROOF	22	REF: SHEET S852
STADIUM	NORTH CONFERENCE CENTER ROOF	200	REF: SHEET S852
STADIUM	CLUB CONCOURSE	130	REF: SHEET S853
STADIUM	PRECAST CLUB SEATING	100	REF: SHEET S853
STADIUM	PREMIUM FLOOR	154	REF: SHEET S854
STADIUM	SOUTH WEST ENTRANCE ROOF	23	REF: SHEET S854
STADIUM	PREMIUM PRECAST SEATING	16	REF: SHEET S854
STADIUM	WEST CONCOURSE	200	REF: SHEET S855
STADIUM	NORTH UPPER CONCOURSE	38	REF: SHEET S855
STADIUM	WEST UPPER CONCOURSE SEATING	23	REF: SHEET S855
STADIUM	NORTH UPPER BOWL SEATING	188	REF: SHEET S855
STADIUM	ANCILLARY ROOFS OVER CONCOURSE	36	REF: SHEET S856
STADIUM	WEST UPPER BOWL SEATING	265	REF: SHEET S857
STADIUM	STRUCTURAL COLUMNS	120	STANDARD WIDE FLANGE, HSS AND PIPE
STADIUM	STRUCTURAL FRAME BRACES	60	HSS REC
STADIUM	PERIMETER PLATE COLUMNS	480	DOUBLE HSS20x12x1/2 AT 28 LOC, TOTAL LEN=3,872'
STADIUM	PERIMETER CLADDING SUPPORT	284	ASSUMED 8 PSF OVER 71,000 SF
STADIUM	SCOREBOARD	267	
STADIUM	SUBTOTAL:	3327	SUMMATION OF ALL STRUCTURAL COMPONENTS
STADIUM	20% DESIGN DEVELOPMENT...	665	
STADIUM	TOTAL:	3992	


STEEL QUANTITY NOTES:

- A 20% TONNAGE ALLOWANCE/CONTINGENCY, IN ADDITION TO LISTED VALUES, FOR FURTHER DEVELOPMENT FROM SCHEMATIC DESIGN HAS BEEN INCLUDED.
- ROOF AND FLOOR STEEL DECK NOT INCLUDED
- QUANTITIES IN THE TABLE ARE FOR THE PRIMARY STRUCTURAL FRAME ONLY AND NO ALLOWANCE IN THE TONNAGE TABLE HAS BEEN MADE FOR THE FOLLOWING:
 - STEEL WASTE DURING THE FABRICATION PROCESS, SUCH AS EXCESS PLATE AND STOCK LENGTH CUT OFFS
 - MISCELLANEOUS STEEL REQUIRED FOR THE SUPPORT AND SERVICING OF MEP EQUIPMENT
 - STEEL STAIRS, INTERMEDIATE LANDINGS AND LADDERS
 - HANDRAILS AND OTHER MISCELLANEOUS METALS
 - TEMPORARY SHORING / BRACING AND OTHER ERECTION AIDS
 - SIGNAGE SUPPORTS, ETC.
 - MECHANICAL EQUIPMENT SUPPORTS, PIPING SUPPORTS, ETC
 - COLD FORMED METAL FRAMING
 - OTHER MISCELLANEOUS METALS AND STRUCTURAL STEEL NOT ASSOCIATED WITH THE PRIMARY SUPPORT OF THE BUILDING STRUCTURE
 - EMBEDDED ITEMS
 - COMPOSITE BEAM STUDS. ASSUME 12" CENTER TO CENTER SPACING FOR ESTIMATING PURPOSES - UTILIZE 3/4" DIA STUDS
 - VERTICAL TRANSPORTATION STEEL
 - HSS AND PLATES ASSOCIATED WITH PRECAST STADIA BEARING SEATS PER PRECAST STADIA TYPICAL DETAILS
 - SLAB AND ROOF EDGE BENT PLATES
- REFER TO SHEETS S851 THRU S857 FOR DETAILED BREAKDOWN OF TONNAGES PER ZONE
- COLUMN WEIGHTS AND CORRESPONDING TONNAGES HAVE BEEN INCORPORATED INTO THE FRAMING CATEGORIES AT EACH LEVEL, EXCEPT FOR THE PERIMETER STADIUM COLUMNS.


STRUCTURAL STEEL TONNAGE AND NOTES

A1

1" = 1'-0"




Project Challenges



Project Challenges





- Schedule
 - Design Assist
 - Changes
- Design
 - Braced Frame Locations
 - Lateral Load Paths
 - Lighting Columns
 - MEP Coordination



Project Challenges

Schedule – Design Assist


- Thornton Thomasetti
 - TEKLA Model
 - Delegated Design
 - Connections
 - Stairs
 - Construction Support
- Worked together to incorporate changes on the fly



Project Challenges

Schedule – Design Assist


- TEKLA Model
 - Shop drawing review
 - Fabrication during review
- Engineer/Fabricator/DA Direction Coordination for Connection Optimization



Project Challenges

Schedule - Changes

- Limiting Design Changes
- Treat like Existing Structure
- Change Orders
- Reuse of purchased Steel




Material In Stock					
Qty	Dimensions	Length	Grade	Loc	Job #
1	C 15 x 33.9	30'-0"	A572-50	J4	3087
1 Total for shape: C					
1	HSS 6 x 6 x 3/8	33'-8 1/2"	A500C	A3	3087
3	HSS 8 x 4 x 3/16	48'-0"	A500C	E4	3087
1	HSS 8 x 6 x 3/8	48'-0"	A500C	C5	3087
1	HSS 8 x 8 x 3/8	40'-0"	A500C	A1	3087
1	HSS 8 x 8 x 3/8	48'-0"	A500C	B6	3087
3	HSS 10 x 10 x 5/16	40'-0"	A500C	B6	3087
1	HSS 10 x 10 x 3/8	30'-0"	A500C	I9	3087
1	HSS 12 x 4 x 3/8	40'-0"	A500C	O2	3087
1	HSS 12 x 4 x 3/8	48'-0"	A500C	D4	3087
13 Total for shape: HSS					

Project Challenges

Design – Braced Frames


- Discontinuities in Load Path
- Finalizing locations took time
- North Endzone Diaphragm



Project Challenges

Design – Lateral Load Paths




- North Endzone Diaphragm



Project Challenges

Design – Lighting Columns


- 2 - HSS20x12x1/2 Cols
- Outboard of building
- Internal conduit
- Braced Frames
- Column lateral Bracing
- CJP/PJP welding on site




Project Challenges

Design – MEP Coordination

- Limited floor to floor heights
- Adding framed openings
- RTUs
- Heavy equipment



Lessons Learned





Lessons Learned

- Schedule
 - Changes in Approach
 - Better Communication
- Design
 - Lateral System
 - Overall Approach
 - Lighting Columns

Changes in Approach

- Estimating Quantities
 - Didn't account for increase in number of pieces
 - Didn't account for shear studs and/or bolts
 - Underestimated the tonnage due to changes
 - Underestimated cost due to complexity
 - Steel already purchased
 - Connections started fabrication
 - 20% Contingency withheld didn't cover overages

Lessons Learned

Better Communication

- Expectations to Owner about Change orders
 - Issuing steel packages 6 mos early
- Having all disciplines invested in early packages
- Understanding the additional effort required
- Being involved in VE discussion
 - Changes impacting structure
 - Net reductions weren't what they thought.

Lessons Learned

Lateral Systems

- Concrete shear walls at elevator cores
 - Reduced the amount of coordination with elevator manufacturer
 - Reduced the amount of coordination locating braced frames
 - Can accommodate different elevator manufacturer easier.

Lessons Learned

Overall Approach

- Being overly conservative or not conservative enough
 - Every ton we save, frees up \$\$ for arch design
 - Focus on connections – Max bolts for shear conn.
- Reduced time to find efficient solutions
 - Limited time for design evolution
 - Experience crew – limited time to mentor
- Push to get the CM onboard at the start of the project

Lessons Learned

Overall Approach

- Being overly conservative or not conservative enough
 - Every ton we save, frees up \$\$ for arch design
 - Focus on connections – Max bolts for shear conn.
- Reduced time to find efficient solutions
 - Limited time for design evolution
 - Experience crew – limited time to mentor
- Push to get the CM onboard at the start of the project
- **DON'T ISSUE BID SETS AT SCHEMATIC DESIGN!!**
 - Quote from Architect, “We are never doing this again”
 - My Response, “Well, we’ve shown that we can”

Lessons Learned

Lighting Columns

- Accounted for 10% of the tonnage (27 Columns!)
- Only one place in the US could roll the columns (curve)
- Present a thermal break challenge being outside the envelope
- Braced Frame connections were complex
- Being outboard of the frame, stability was a challenge
- Was there a better solution?

Lessons Learned

Level of Effort

- 16000 total SE hours
- 1800 hours of OT
- Three offices (KC, LA & SEA)
- 23 Different Struc. Engineers
- Peak – 13 Engineers
- Estimate 15% additional effort due to project acceleration
- **>> Original Plan was 5 FTE**



Acknowledgements

Construction Manager at Risk: Turner Construction Company; Kansas City, MO
Steel Fabricator and Detailer: Doherty Steel; Paola, KS
Concrete Contractor: George J Shaw Construction; Kansas City, MO
Design Assist Engineer: Thorton Thomasetti Group, Kansas City, MO
MEP&FP Engineers: Henderson Engineering; Lenexa, KS
Structural Engineer: HNTB Architecture; Kansas City, MO
Architect: HNTB Architecture; Kansas City, MO
Associate Architect: Multistudio; Lawrence, KS
Owner: The University of Kansas



Questions?
